



Addendum No. 2
Page 1 of 1

DATE: February 4, 2025

Joliet Junior College
1215 Houbolt Road
Joliet, IL 60431

TO: Prospective Bidders
SUBJECT: Addendum No. 2
PROJECT NAME: **Automotive Exhaust Duct Extension**
JJC PROJECT NO.: B25015

This Addendum forms a part of the Bidding and Contract Documents and modifies the original bidding document as posted on the JJC website. Acknowledge receipt of this addendum in the space provided on the Bid Form. FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION.

Questions Received:

1. Can you provide the sign in sheet for the job walk?
Answer: No contractors attended the optional site walk-through.
2. For bidding purposes please advise on the existing floor thickness we should consider for concrete floor removal.
Answer: Existing concrete is 5" thick.
3. For bidding purposes are overcuts permitted for concrete floor removal?
Answer: Yes
4. Please confirm the required centers on rebar dowels, 18" or 24"? Is rebar mat required for the trench or just the large area at tie in?
Answer: There are both. The #4 bars each way at 18" on center in the slab filled areas (both) and the ½" bars dowels staggered at 24" on center into the slab on sides. Just as it reads (Typical).

End of Addendum #2